ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 9th June 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 6th July 1931, for increasing the capacity of Pombarahalli Bylakere Reg. No. 770 of Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for increasing the capacity of Pombarahalli Bylakere, Reg. No. 770 of Mulbagal Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderers must quote specific rates for each item of the work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate of quantities for increasing the capacity of Pombarahalli Bylakere, Reg. No. 770, Mulbagal Taluk:—

Sl. No.	Items of work	Per	Quantity	Total
	Bund at R. L. 58·00.			Rs.
1	Earthwork to bund including watering and tamping ...	C.yd.	11,226	
2	Turfing do do ...	S.yd.	10,677	
3	Supplying and fixing grade stones including cutting figures and painting, etc.	Each	17	
4	Chiselling figures painting and re-fixing old grade stone	,,	28	
5	Cutting trenches in old bund for grips of new earth ...	Grade	32	
6	New stone revetment with new jelly	C.yd.	956	
7	Gravel backing behind revetment ...	,,	316	
8	Chiselling and painting old register No. stone ...	Each	1	
9	Providing a gauge stone including cutting figures, painting, etc.	,,	1	
	Sluice.			
1	Petty repairs and providing new plug and rod with locking arrangement.	Each sluice	2	
	Waste weir at R. L. 53·00.			
1	Removing and resetting coping slabs in surki mortar ...	S.ft.	191	
2	Burnt brick in surki mortar	,,	1,322	
3	Plastering with surki mortar	Sq.	14·19	
4	Concrete in surki mortar	S.ft.	56	
5	Removing and resetting apron	C.yd.	25	
6	New stone revetment (laterite)	,,	2	

H. R. VENKATASUBBA RAO,
Executive Engineer.